BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 58

Name of Work:-Repairs and maintenance of BBMP office building in ward no 04Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri MANJUNATH A V	
				Rate	Rate in Words
1	KSRB15--15.1: Providing and applying painting in two coats with plastic emulsion paint of approved brand and shade on surface to give an even approved shade after thoroughly bruising the surface, fee from mortar droops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. [P .113 I No15.51.2] @50.00	Sqm	3051.23	70.00	Rupees seventy only
2	KSRB15-17..6: Providing and applying painting two coats (excluding priming coat) on new wood surface and/or wood based surface with enamel paint to give and even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labourcomplete as per specifications -do- (P.102/15.60.1)	Sqm	34.65	75.00	Rupees seventy five only
3	KSRB 11-17-1: Providing and fixing C.P Brass towel rail 740 mm length , 20mm dia with C.P brackets fixed to wooden cleats with C.P brass screws including cost of materials labour complete as per specifications.(P.70/12.45)-	Unit	2.00	770.00	Rupees seven hundred seventy only
4	KSRB 13-6.3-1: Providing and fixing in position brass gate vaive with CI wheel of approval quality (Screw end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS13.2.2/13.3(P.79/13.34)	Unit	1.00	590.00	Rupees five hundred ninety only
5	Supplying patty type flourscent tube light fitting of 4-36/40 watts fluresent tube fitting., made out of M.S sheet and stove enarneld with low loss open construction copper woundferrmagnetstic ballast, starter, locking type brass contact holders mounted on double fold type sheet base fully wires for use on 230 volts A C supply including I No 4-36/40watts fluorscent tube- Groub-B	Each	2.00	940.00	Rupees nine hundred forty only
6	Supplying capacitor type celling fan complete with down and blades shackle, canopies etc., for operation on 230 volts, 50 cycles, Single phase AC supply confirming to ISS-374-1979 and with double ball bearing system (ch-03)(P-23) sl.no.23)	Each	4.00	1700.00	Rupees one thousand seven hundred only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri MANJUNATH A V	
				Rate	Rate in Words
7	Fixing a ceiling / Wall mounting fan of all capacities and all types to the existing S hook together with supplying and fixing a 5 amperers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely.	Each	4.00	71.00	Rupees seventy one only
8	KSRB 10-3 : Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofingcompound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials, labour complete as per specifications	Sqm	180.00	868.00	Rupees eight hundred sixty eight only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.